

Tule Subbasin Technical Advisory Committee

July 17, 2019

Prepared for:
Tule Subbasin Technical Advisory Committee

Thomas Harder & Co.
Groundwater Consulting



Status of Work Performed Since April 2019 – Projects and Management Actions

Eastern Tule GSA

No.	Lead Entity	Project Name	Description	Timeframe	Annual Volume	Water Source	Confidence
1	City of Porterville	Population Increase	Increase GW Production	2.5%/yr 2020-2040	9,500 a/yr by 2040	N/A	High
2	City of Porterville	Recycling Increase	Increase RW Applied to Ag	2.5%/yr 2020-2040	1,900 a/yr by 2040	Recycled Water	High
3	City of Porterville	Recycling Increase	Increase RW Recharge	2.5%/yr 2020-2040	1,600 a/yr by 2040	Recycled Water	High
4	City of Porterville	Tule River Recharge	Recharge Project	Starting 2019/20	900 a/yr	Tule River	High
5	City of Porterville	FKC Recharge	Recharge Project	Starting 2020/21	1,100 a/yr	FKC via Porterville ID	High
6	Porterville ID	SA 1 & 2	Expand distribution system	Starting 2018/19	3,200 a/yr	Tule River and FKC	High
7	Porterville ID	Falconer Bank	Develop water bank	Starting 2020/21	3,300 a/yr of leave-behind	FKC and others	High
8	Porterville ID	Recharge Policy	On-Farm recharge	Starting 2019/20	3,000 a/yr	Tule River and FKC	High
9	Saucelito ID	Conway Bank	Develop water bank	Starting 2020/21	1,100 a/yr of leave-behind	FKC and others	High
10	Saucelito ID	Recharge Policy	On-Farm recharge	Starting 2019/20	2,000 a/yr	FKC	High
11	Kern-Tulare WD	In-District Pricing	Pricing change	Starting 2020/21	2,600 a/yr	N/A	High
12	Kern-Tulare WD	Reservoir Storage	Surface water storage	Starting 2029/30	500 a/yr	FKC and others	Medium
13	Kern-Tulare WD	CRC Pipeline	Deliver produced water	Starting 2024/25	680 a/yr	CRC Produced water	High
14	Terra Bella ID	Deer Creek Recharge	Divert and recharge DC	Starting 2017/18	800 a/yr	Deer Creek	High
15	PWC, VWD, & CMDC	SREP	Success Dam Enlargement	Starting 2024/25	400 a/yr	Tule River	High
16	Hope WD	In-District Recharge	Recharge Project	Starting 2022/23	5,000 a/yr every 3 years	FKC and others / unknown	Medium
17	Ducor ID	In-District Recharge	Pipeline and Recharge Project	Starting 2023/24	4,000 a/yr	FKC and others / unknown	High

LTRID GSA

No.	Project Name	Description	Timeframe	Annual Volume	Water Source	Confidence
1	Creighton Ranch	Groundwater exports	Unknown	Unknown	Not applicable	N/A
2	LTRID - Pixley ID FKC	Continue FKC transfers to Pixley ID	Ongoing	To be determined	FKC	N/A
		SREP	Success Dam Enlargement	Starting 2024/25	2600	Tule River

Pixley GSA

No.	Project Name	Description	Timeframe	Annual Volume	Water Source	Confidence
1	LTRID - Pixley ID FKC	Continue FKC transfers from LTRID	Ongoing	To be determined	FKC	N/A

DEID GSA

No.	Project Name	Description	Timeframe	Annual Volume	Water Source	Confidence

Tri-County GSA

No.	Project Name	Description	Timeframe	Annual Volume	Water Source	Confidence
1	Deep Pumping Reduction	Replace deep pumping with 24 new shallow wells	Start In 2019/20, completed In 2023/24	24,000 a/yr	Not applicable	N/A
2	Duck Club Project	Duck Club water transferred to farms	2019/20	5,400 af every 7 years	Unknown	N/A
3	Liberty Project	Participation in the Liberty Project surface water storage	Start In 2019/20, completed In 2022/23	5,000 a/yr	FID, FKC, KR, TR, KW, SWP	N/A
5	Recharge Scenario	Confidential. Capture and recharge flood water.	Unknown	1,200 to 1,800 a/yr	Unknown	N/A
6	Groundwater Exports	Groundwater Exports	Unknown	Unknown	Unknown	N/A

Alpaugh GSA

No.	Project Name	Description	Timeframe	Annual Volume	Water Source	Confidence
1	Water Capture	Deer Creek flood capture	Starting In 2022/23	1,100 af 2.5x per yr every 2 yrs	Deer Creek	N/A
2	Cropping Changes	Install drip irrigation on 1,900 acres	Starting 2019/20 ?	Not applicable	Not applicable	N/A



Status of Work Performed Since April 2019 – Transitional Pumping Schedules

Planned Transitional Pumping by GSA

	Eastern Tule GSA 2	LTRID GSA A	Pixley ID GSA A	DEID GSA -	Tri-Co GSA -	Alpaugh GSA -
2020-2025	90% of over-pumping	2.0 af/ac Over Cons. Use Target	Fallow 5,000 acres; Remaining no change	No Change	No Change	Reduce cropped acres by 880 acres
2025-2030	80% of over-pumping	1.5 af/ac Over Cons. Use Target	Fallow 5,000 acres; Remaining 1.5 af/ac Over Cons. Use Target	Linear Transitional Pumping (Annex Management Area)	Reduce pumping 10,000 af/yr	
2030-2035	30% of over-pumping	1.0 af/ac Over Cons. Use Target	Fallow 5,000 acres; Remaining 1.0 af/ac Over Cons. Use Target			Sustainable
2035-2040	Sustainable	0.5 af/ac Over Cons. Use Target	Fallow 5,000 acres; Remaining 0.5 af/ac Over Cons. Use Target			
2040+		Sustainable	Sustainable			

Table 2-6 of Subbasin Setting Report


Three Project and Management Action Scenarios Analyzed with the Model
and Submitted May 31, 2019

Status of Work Performed Since April 2019 – Land Subsidence Analyses

- Draft Report of Detailed Analysis of Land Subsidence Along the Friant-Kern Canal – Submitted May 24, 2019

Status of Work Performed Since April 2019 – Model Uncertainty Analysis and Sustainable Yield

Uncertainty Analysis 2040/41 through 2049/50 Average Sustainable Yield




*Percentile runs

Preliminary Draft – For Discussion Purposes Only



Comparison of Elements of the Sustainable Yield

Elements of the Sustainable Yield over Time




Notes:

Historical is 1990/91 through 2009/10


Future is 2040/41 through 2049/50

*Sub-surface Outflow is negative in the Sustainable Yield equation

As Groundwater Levels Stabilize in the Future, Less Water Will Be Captured and More will be Lost



Projected Change in Groundwater Storage



Status of Work Performed Since April 2019 – Land Subsidence Analyses

- Draft Subbasin Setting Report Submitted on June 20, 2019
- Draft Tule Subbasin Monitoring Plan Submitted on June 21, 2019

Next Steps and Schedule

- Address Comments to the Subbasin Setting Report and Monitoring Plan Including:
 - Revisions to Some Hydrology Assumptions
 - Revisions, as Necessary to Some Water Budget Terms
 - Analysis of Consumptive Use Target that Won't Result in Long-Term Negative Change in Groundwater Storage
 - Adjusting Minimum Thresholds and Measurable Objectives
- Revised Subbasin Setting to be Submitted August 16, 2019



Next Steps and Schedule

- In Parallel with Revisions to the Subbasin Setting, On-Going Work is being Conducted to Address Mitigation of Land Subsidence at the Friant-Kern Canal

Questions